

ITC Midwest LLC Response to Deficiency Letter Dated May 15, 2013
Docket No.: E-20994, AM14
Midway to Lafayette
Linn County

Petition

- Revised as suggested.
- Revised as suggested.

Exhibit A

- Revised as suggested.

Exhibit B

- Revised as suggested.

Exhibit C – Segment 1 of 2

- The nominal operating voltage was changed from 69kV to 34.5kV. The maximum operating voltage will remain 72.5kV.

Exhibit C – Segment 2 of 2

- The nominal operating voltage was changed from 69kV to 34.5kV. The maximum operating voltage will remain 72.5kV.
- Drawing for grain bin clearance near Otter Road has been attached.
- Drawing for LP tank clearance has been attached.
- Drawing for clearance to tree house has been attached. Distribution will be installed on alley arm and transmission will be framed to one side away from tree house to add additional clearance. The landowner was approached about tree trimming and they are okay with trimming for clearance.

Exhibit D

- This was addressed in the Exhibit C's.
- Additional information has been provided explaining possible use of alternative routes and methods of supply.

RECEIVED
June 4, 2013

E-20994
(Amendment No. 14)